Table 2: Shutdown, Isolation, Deenergization and Verification

Colors Key

- **Table 1: Scope** — (blue)
- **Table 2: Shutdown** — (purple)
- **Table 3: Lockout/ Tags-plus Program** — (red-orange)
- **Table 4: Multi-employer** — (orange)
- **Table 5: Group** — (light blue)
- **Table 6: Removal Testing, Startup** — (teal)
- **Coordinator:** — (white box, dark red border)
- **Navy Notes:** — (white box, blue dashed border)
- **Navy/Coordinator Combined** — (white box, combined border)

From Table 1 Scope and Application

From Table 6 Testing

Ensure that the authorized employee has knowledge of the hazards and controls (e)(1)(i)(A)-(C)

Notify each affected employee of planned machine or system shutdown and deenergization (e)(1)(ii)

Is the host employer the Navy?

Yes → Navy ship's force shuts down and isolates the system [Note to (e)]

Contract employer verifies deenergization and isolation [Note to (e)]. Each authorized employee must be given the option to verify deenergization and isolation (g)(3)

No → Perform an orderly shutdown according to the established written procedures (e)(2)-(3)

Render safe all potentially hazardous energy (e)(4)

Verify deenergization of machinery, equipment, or system and isolation of all energy sources prior to servicing (g)(1)

To Table 3 Implementation of a Lockout / Tags-plus Program